

2026 Takao Rock 打狗祭 Hi-ing5 週邊舞台硬體統籌與現場 執行服務 需求說明書

壹、主旨：

高雄流行音樂中心預計於 2026 年下半年舉辦開幕五周年慶祝活動。為增加媒體露出機會，俾利於中心營運打響園區品牌形象，促進場館利用率，帶動高雄音樂市場發展，本中心爰辦理「2026 Takao Rock打狗祭-Hi-ing5」活動，本案為本活動依演出藝人演出現場之舞台、燈光、音響、電力、視訊、路口意象及週邊配備及人員等之硬體需求，擬委託專業廠商執行服務。

貳、經費預算：新台幣 3,800,000 元（含稅）。

參、執行地點：

一、海風舞台：高雄流行音樂中心_海風廣場，詳細空間配置請參閱：

附件 1：2026 海風廣場_全區平面圖

附件 2：2026 海風廣場_平面圖與電力配置圖

二、珊瑚舞台：高雄流行音樂中心_珊瑚礁群，詳細空間配置請參閱：

附件 3：2026 珊瑚礁群_場域平面圖

三、海膽舞台：音浪塔中庭

附件 4：2026 音浪塔平面圖

肆、履約期程：

一、自決標次日起至 115 年 11 月 10 日，此期限包含：

- 活動日：115 年 10 月 10 日、10 月 11 日
- 進場日（暫訂）：115 年 10 月 4 日起
- 繳交成果報告資料：115 年 11 月 10 日前

二、決標次日起廠商應配合本中心參與相關製作會議、協助資料製作提供與現場場勘等相關行政事宜。

三、廠商應於演出活動後 2 日內（115 年 10 月 13 日下午 21 時前）完成硬體

拆除與場地回復。

四、115 年 10 月 10、11 日演出活動結束後 30 日內（115 年 11 月 10 日）提供本案成果報告書（書面一式 2 份及電子檔一份）辦理驗收。

伍、需求說明：

本案提案內容至少應包括（但不限）以下需求項目之具體規劃執行方式，提案廠商可提供更具效益之執行規劃，經本中心同意後執行。

一、時間：演出活動暫訂暫定於 115 年 10 月 10 日（星期六）至 115 年 10 月 11 日（星期日）共 2 日。（115 年 10 月 10 日為 14 時至 23 時、115 年 10 月 11 日 則為每日 14 時至 23 時 00 分），實際執行時程，依本中心需求為主。

二、廠商應於上述活動時間，負責本活動各舞台燈光、音響、視訊工程、特效、電力等工程及相關技術人員與現場活動執行服務。

三、舞台設計及工程規劃：

（一）舞台設計應能充分發揮本中心海洋意象及音樂祭活動美學之創意設計並應融合科技視覺呈現為核心，廠商投標時應附各舞台模擬圖或能呈現設計創意、規格之相關圖說。舞台大小及相關設備可視場地實際情況經本中心同意後調整。

（二）舞台設計及製作執行需包含協助提供本中心舊有充氣物修補、充氣，另應協助本中心充氣物及硬體各類帳篷與桌椅需求。廠商得運用本中心現有充氣物規劃設計（詳如附件 5：2026 高流充氣物一覽表）。

（三）本活動預計委託廠商配合本中心引導與各舞台區域方位之識別需要，於活動場域範圍搭設活動時間表及場域圖或贊助廣告牆合計至少 3 座（包含至少 4 面露出），並運用本中心舊有充氣物至少 2 只，規劃設計佈置具有打狗祭形象的獨立式精神堡壘至少 1 座及建置海風廣場入口意象 1 座，以提供民眾拍照打卡，增加活動氛圍與話題性（各配置點位暫訂如附件 6：2026 周邊裝置物點位）。

（四）舞台結構搭設施工強度需提供結構技師簽證或結構安全檢核證明，

並依高雄市臨時展演場所臨時建築物設置辦法向高雄市政府工務局建築管理處申請許可，施工時依簽證之圖說辦理，並有訓練合格之人員於現場指揮監督搭設及拆裝台作業，佈場與撤場日期應與本中心協商合議後執行。

- (五) 進場及撤場施工應注意場地設施及環境維護，必要時，應設置保護地墊，避免造成永久性至破壞，如有造成毀損情事，應負回復原狀及相關賠償責任(廠商進場施工前如發現場地設施已有損壞情形，應就場地設施現況拍照存證並通知本中心)。

四、音響工程規劃：

- (一) 應就本活動場域各舞台提出具體規劃執行方式：

- 海風舞台、珊瑚舞台及海膽舞台：

提出符合高雄流行音樂中心海風廣場、珊瑚礁群場域及音浪塔中庭之音場設計規劃，並確保演出活動聲音品質。

- (二) 應就本中心邀約之演出團體、樂團及藝人之硬體需求，提出包含(但不限)於外場擴音系統、舞台監聽系統、現場收音系統、樂器及設備器材，並應提供相關現場舞台音控、外場音控及技術等人員。

五、燈光工程規範：

- (一) 燈光設計應能配合發揮本中心辦理音樂祭活動美學之創意設計並應融合科技視覺呈現為核心、海風舞台須符合高雄流行音樂中心規劃之燈光設計圖(詳如附件 7：2026 海風舞台燈圖)，其餘舞台則由廠商自行設計。廠商投標時應附燈光模擬圖或能呈現設計創意、規格之相關圖說。

- (二) 燈光執行及燈光工程相關設備需視場地各舞台及各演出團體風格實際情況設計規劃，經本中心同意後規劃執行。

- (三) 廠商應於活動時，提供相關燈光技術人員協助本中心活動進行。

六、視訊工程規劃：

- (一) 海風舞台：2 面至少 300 吋 LED(PGM 畫面)；後台區域放置 Monitor。

- (二) 應就表演節目內容(包含但不限於演出、開場、換場等)，執行切換相關視訊內容素材，並應提供視訊相關服務及技術人員。

其他：

- (一) 本活動演出團體、樂團及藝人由本中心決定並進行邀約，廠商應配合本活動各舞台之舞台監督及執行團隊。
- (二) 廠商需配合本中心共同討論演出節目之流程和整體規劃，所有執行規劃需經本中心核可後方可執行。
- (三) 本案規劃與執行工作需與本中心密切協調及全力配合，廠商應指定 1 名以上專案人員進行專案管理，不定期召開本中心工作會議報告，並協調配合相關事項。
- (四) 廠商應配合本中心場佈、搭台、測試、彩排及撤場時間，安排本活動所需之排練、技術調整等事宜。
- (五) 廠商應投保必要之保險，相關保額規定，詳如本案契約規定

海風舞台（基本配置至少須符合以下需求）：

項目	分類	器材規格	數量	單位
結構設備	Roof Structure	W18m x D12m Truss Roof	1	Unit
	Lighting Truss	Box Truss	80	Meter
	Electric Hoist	1 Ton Hoist	30	Unit
	Hoist Controller	12 ch Hoist Controller	1	Unit
樂器設備	Music Instrument	Guitar Amp 1	3	Unit
		Guitar Amp 2	3	Unit
		Bass Amp 1	2	Unit
		Bass Amp 2	2	Unit
		Drum Set 1	2	Unit
		Drum Set 2	1	Unit
		Keyboard Set 1	3	Unit
		Keyboard Set 2	3	Unit
舞台設備	Stage Structures	210cm Box Layher Structures x H16m ~ H18m	1	Unit
		Main Stage W 1820cm x D 1638cm x H 120cm	1	Unit

項目	分類	器材規格	數量	單位
		Secondary control stage W 1183cm x D 816cm x H 120cm	1	Unit
		8ft x 8ft Rolling Riser	4	Sets
		250m2 Black Marley floor	1	Unit
		250m2 Black Carpet	1	Unit
		W 1800cm x H 150cm Black Drape	1	Unit
		W 210cm x H 11m ~ H 16m Black Drape	1	Unit
		Crowd Control Stage Barrier	1	Unit
		Ego Riser	5	Pcs
燈光設備	Moving Light	1200W Spot Moving Light	36	Pcs
		400W LED Wash	36	Pcs
		400W Sharpy	48	Pcs
		120W TB5 IP, tornado	36	Pcs
	General Light	4 Light Blinder	12	Pcs
		RGB LED Strobe	24	Pcs
	Special Effects	Smoke Hazer	6	Pcs
	Lighting Console	Digital Lighting Console	2	Unit
	Follow Spot	2000W Follow Spot	2	Pcs

項目	分類	器材規格	數量	單位
	Intercom	Intercom System	1	Unit
音響設備	Front of House	3-way active, dual 12" Main Line Array Speaker	2	Sets
		3-way active, dual 12" . Out Fill Line Array Speaker	2	Sets
		2-way active, dual 8". Front Fill Speaker	1	Sets
		Bass-reflex, dual 15' '. FLY Subwoofer Speaker	2	Sets
		Reference high power subwoofer, dual 18". Ground Subwoofer Speaker	1	Sets
	Monitor System	2-way active, 15". Monitor Speaker	12	Pcs
		Wireless IEM System	12	Units
	Wireless & Pick Up	Wireless Microphone System	8	Units
		Instrument Microphone	1	Unit
	Audio Mixer	Digital Audio Mixer. Input 72 / Output 48. (FOH · MON)	4	Units
電力設備	Power Support	3Ø4W Cable Run	1	Unit
		3Ø5W Cable Run	1	Unit
		1Ø3W Cable Run	1	Unit
人員	Engineer & Production	Lighting Engineer	1	Pax
		Audio Engineer	2	Pax
		Stage Designer	8	Pax

珊瑚舞台（基本配置至少須符合以下需求）：

項目	分類	器材規格	數量	單位
結構設備	Roof Structure	W12m x D6m Truss Roof (Module $\geq$ 30cm)	1	Unit
	Electric Hoist	1 Ton Hoist	8	Units
	Hoist Controller	12 ch Hoist Controller	1	Unit
樂器設備	Music Instrument	Guitar Amp 1	2	Unit
		Guitar Amp 2	1	Unit
		Bass Amp 1	2	Unit
		Bass Amp 2	1	Unit
		Drum Set	2	Unit
		Keyboard Set	3	Unit
舞台設備	Stage Structures	210cm Box Layher Structures x H 6m ~ 8m	1	Unit
		Main Stage W 1200cm x D 600cm x H 150cm	1	Unit
		W 1200cm x H 150cm Black Drape	1	Unit
		W 210cm x H 6m ~ H 8m Black Drape	1	Unit
		Crowd Control Stage Barrier	1	Unit
燈光設備	Moving Light	500W LED BSW Moving Light	36	Pcs
		350W Wash Moving Light	36	Pcs
	General Light	4 Light Blinder	6	Pcs
		RGB LED Strobe	16	Pcs

項目	分類	器材規格	數量	單位
		Key Light System	1	Unit
	Special Effects	Smoke Hazer	2	Pcs
	Lighting Console	Digital Lighting Console	1	Unit
音響設備	Front of House	3-way active, dual 12" Main Line Array Speaker	2	Sets
		2-way active, dual 8" Front Fill Speaker	1	Sets
		Reference high power subwoofer, dual 18". Ground Subwoofer Speaker	1	Sets
	Monitor System	2-way active, 15". Monitor Speaker	10	Pcs
		Wireless IEM System	1	Units
	Wireless & Pick Up	Wireless Microphone System	2	Units
		Instrument Microphone	1	Unit
	Audio Mixer	Digital Audio Mixer Input 72 / Output 48	1	Units
電力設備	Power Support	Diesel engine generator	2	Unit
		304W Cable Run	1	Unit
		305W Cable Run	1	Unit
		103W Cable Run	1	Unit
人員	Engineer & Production	Lighting Engineer	1	Pax
		Audio Engineer	2	Pax
		Stage Designer	4	Pax

周邊帳篷結構（基本配置至少須符合以下需求）：

項目	分類	器材規格	數量	單位
電力設備	Power Support (For Tent)	1Ø3W Cable Run	1	Unit

海膽舞台（基本配置至少須符合以下需求）：

項目	分類	器材規格	數量	單位
結構設備	Roof Structure	W4m x D4m Tringle Truss Roof (Module $\geq$ 30cm)	1	Unit
舞台設備	Stage Structrues	Main Stage W 360cm x D 360cm x H 120cm	1	Unit
電力設備	Power Support	1Ø3W Cable Run	1	Unit
燈光設備	Moving Light	500W LED BSW Moving Light	12	Pcs
		350W Wash Moving Light	12	Pcs
	General Light	Key Light System	1	Unit
		RGB LED Par	24	Pcs
	Special Effects	Smoke Hazer	2	Pcs

項目	分類	器材規格	數量	單位
	Lighting Console	Digital Lighting Console	1	Unit
音響設備	Front of House	Main Speaker	1	Unit
		Ground Subwoofer Speaker	1	Unit
	Monitor System	Monitor Speaker	4	Pcs
	Wireless	Wireless Microphone System	1	Units
	Audio Mixer	Digital Audio Mixer	1	Units
樂器設備	Music Instrument	Disc Jockey Set	1	Units
		Instrument Microphone	1	Unit
		Mic stand	15	Pcs
		Bass Amp	2	Unit
		Drum Set	1	Unit
		Keyboard Set	2	Unit
		Guitar Amp	2	Unit
裝置藝術	Balloon	Match the stage proportions	1	Pcs
	Inflatable Device	Blowing Machine	1	Units
人員	Engineer & Production	Lighting Engineer	1	Pax
		Audio Engineer	1	Pax
		Stage Designer	1	Pax